

Gaines Water Installation

Regulations:

- Water lines shall be one inch type K copper water tube, or one inch plastic with 200 pound test.
- Water lines shall be a minimum of a depth of 4 feet (48 inches.)
- Water tube is to be bedded and covered with select earth, no rocks, ashes or cinders. Sand may be required in rocky areas.
- Plastic water tube must have a #10 copper tracer wire from the curb stop at the road to the water meter in the house.
- If plastic is used, it must be one piece, no couplings will be allowed. Metal inserts are to be used with the plastic water tube.
- Lines that run over 200 feet must have a meter pit. Town will install the meter pit, the customers will be responsible for the cost.
- NOTE: All lines are to be inspected and tested by the Gaines Water Department before they are back-filled.
- Water Department must have three working days (3) notice for inspections.
- Water meter assembly charge: Before water is turned on, homeowners will have to have paid for the water meter assembly. \$300.00 payable at the Town Clerk's Office during normal working hours.
- Water Department or Certified Plumber will install meters. The meter assembly includes the meter, shut off valve and the back-flow preventor.
- By order of the New York State Health Department: Before any water is turned on, all other sources of water must be disconnected completely from the Town water system.
- We recommend the homeowner purchase a pressure regulator.
- If you have any questions, please call Ronald Mannella at 589-5833.

Thank You

El pueblo de Gaines:

- La instalación de Riega las Líneas
- Las líneas de flotación serán un tubo de tipo pulgada de agua de cobre K, o un plástico de pulgada con 200 prueba de la libra.
- Las líneas de flotación serán un mínimo de una profundidad de 4 pies (48 pulgadas).
- El tubo del agua es de ser bedded y para ser cubierto con la tierra selecta, ningunas piedras, las cenizas ni las carbonillas. La arena puede ser requerida en áreas rocosas.
- El tubo plástico del agua debe tener un #10 cobre alambre trazador del limita la parada en el camino al contador de agua en casa.
- Si plástico es utilizado, debe ser un pedazo, ningunas parejas serán permitidas. Las adiciones del metal son de ser utilizadas con el tubo plástico de agua.
- Las líneas que desbordan 200 pies deben tener un hoyo de metro. El pueblo instalará el hoyo de metro, los clientes serán responsables del costo.
- La NOTA: Todas líneas son de ser inspeccionadas y para ser probadas por el Departamento de Agua de Ganancias antes ellos son rellenos.
- El Departamento del agua debe tener tres días de trabajo (3) nota para inspecciones.
 - Riegue la carga de la asamblea de metro: Antes agua es prendida, propietarios tendrán que haber pagado por la asamblea de contador de agua. \$300,00 pagadero en la Oficina de secretario del ayuntamiento durante trabajar normal horas.
 - Riegue el Departamento o Plomero Certificado instalará metros. La asamblea del metro incluye el metro, apagó válvula y el preventor de reflujo.
 - Por orden del Departamento de la Salud del Estado de Nueva York: Antes cualquier agua es prendida, todas las otras fuentes de agua deben ser desconectadas completamente del sistema de agua de Pueblo.
 - Recomendamos que el propietario compre un regulador de la presión.
- Si usted tiene cualquier pregunta, por favor llamada Ronald Mannella en 589-5833.

Gracias